

**DEPARTMENT OF FIRE-SAFE SUSTAINABLE BUILT
ENVIRONMENT****Fire Laboratory and Fire Engineering**

Požarni laboratorij, Obrtna cona Logatec 35, 1370 Logatec

Member of egolf - European Group of Organisations for
Fire Testing, Inspection and Certifications**SLOVENSKA
AKREDITACIJA**
SIST EN ISO/IEC 17025
LP-005**TEST REPORT
241/22-530-1-EN****FIRE RESISTANCE TEST**of a 200 mm thick semi pre-fabricated lightweight
loadbearing concrete ceiling slab**MARANA EUROPAN**Orderer: **MARANA d.o.o.,
Kurtovići 21, HR-21231 Klis, Croatia**Order/contract: **Offer No. 557/2020/17. 6. 2020**Responsible investigator: **Simon Grum, mag. inž. str.**Head of laboratory: **Friderik Knez, univ. dipl. fiz.**Director: **doc. dr. Aleš Žnidarič, univ. dipl. inž. grad.**

Date:

The report was internally reviewed and approved by all listed persons, which is confirmed by the electronic signature. Document authenticity
check: www.zag.si/pristnostThe results of the tests refer only to the tested specimens. This report may only be reproduced as a whole. Complaints will be considered only if
received within 15 days from the date of issue of this report..
Total number of pages: 38; number of annexes: 7.

Table of contents

1. General	3
2. Sampling	3
3. Description of the product.....	3
3.1 Composition of the test specimen.....	3
3.2 Composition of the supporting construction	4
3.3 Sealing materials.....	4
3.4 Composition of the additional sample panel	4
3.5 Number of test specimens.....	4
3.6 Applied loading.....	4
4. Conditioning of the specimen	5
5. Date of test.....	5
6. Testing procedure	5
6.1 Test conditions	5
6.2 Temperature inside the furnace.....	5
6.3 Preliminary measurements.....	5
6.4 Overpressure inside the furnace	5
6.5 Temperature rise on the unexposed surface of the test specimen.....	6
6.6 Deflection of the test specimen	6
6.7 Deviations from the testing procedure	7
7. Observations during the test.....	7
7.1 Visual observation.....	7
7.2 Deflection of the test specimen	7
7.3 Integrity	8
7.4 Insulation.....	8
7.5 Load-bearing capacity	8
8. Test results.....	8
9. Field of direct application of tested results.....	9
9.1 Moments and shear forces	9
10. Annexes	9

1. General

Product: 200 mm thick semi pre-fabricated lightweight loadbearing concrete ceiling slab **MARANA EUROPAN**

Supplier: **MARANA d.o.o.**, Kurtovići 21, HR-21231 Klis, Croatia

Manufacturer: **MARANA d.o.o.**, Kurtovići 21, HR-21231 Klis, Croatia

2. Sampling

The test specimen was sampled and delivered by the supplier to the Fire laboratory on 13th March 2023.

Sample No.: P23/044

3. Description of the product

All dimensions in test report are in millimetres.

Supplier delivered one 200 mm thick pre-fabricated loadbearing ceiling **MARANA EUROPAN**, of dimensions 2190 × 6800 × 200. In addition to test specimen, one sample of filling element dimensions 675 × 600 × 145 was delivered to the laboratory.

The test specimen was closing the top opening of a combo furnace of dimensions 4000 × 6000 × 4000. The part of the furnace that was not covered by the test specimen was covered with aerated concrete slabs.

3.1 Composition of the test specimen

Test specimen was light slab construction made of pre-fabricated elements. The loadbearing of the slab was provided using four main beams, positioned 680 mm apart, with a width of 120 mm and a thickness of 35 mm. Distance between the top and the bottom reinforcement was 160 mm. In the main beam, three reinforcement bars with a diameter of 14 mm and two reinforcement bars with a diameter of 10 mm were placed. The diameter of the top reinforcement bar was 10 mm. In between main beams, filling elements of dimensions 600 × 680 × 150 mm were placed on the beams. On top, top-zone reinforcement mesh Q 196 was placed over the entire surface of the slab. In between filling elements, perpendicular reinforcement Ø8 mm beam bars were placed in top- and bottom-zone. Top surface and all cavities between filling elements were cast with C25/30 concrete (in Annex No. 6 compressive strength test report from 29. 11. 2021). Measured moisture content at the day of the test in the concrete was 1,6 moisture content in % of dry weight. Measurement was made close to the centre of the test specimen with Gann Hydromette HT 85 T.

Filling elements were made of formed KEMOPOR EPS100 blocks (declaration of conformity in Annex No. 6) with a thickness of 125 mm, produced by the company Kamenović d.o.o., that were casted with Keramzit (Liapor) C16/20 concrete with expanded clay aggregate, produced by the company Lias Österreich GesmbH (certificate in Annex No. 6). Keramzit concrete was reinforced over the entire surface of each filling element with 50 × 50 mm grid galvanized mesh with 2 mm diameter bars.

Details of the test specimen are shown in the documentation provided by the sponsor in Annex No. 6.

3.2 Composition of the supporting construction

Test specimen was positioned on two steel beams HEA 160, of dimensions 152 × 160 × 2180 mm. Over each HEA 160 beam, 25 mm thick ceramic wool was laid in order to protect the supporting construction from heat exposure. In addition to ceramic wool, mineral wool lamellas were placed in the cavity of each beam. Test specimen was laid on top of each insulated beam. In addition to the ceramic wool insulation, rock wool slabs of dimensions 100 × 160 mm were placed in front of each support beam towards the opening in the frame.

The distance between the centres of the supports was 6400 mm.

3.3 Sealing materials

Gaps and cavities between the test specimen and the aerated concrete slabs, placed at the sides of the test specimen, were sealed by means of 25 mm thick ceramic wool in such a way that bending of the test specimen was allowed.

3.4 Composition of the additional sample panel

The supplier provided one additional sample of filling element dimensions 675 × 600 × 145.

The additional filling element sample had following structure:

- thickness of the sample was 145 mm;
- filling elements were made of formed 125 mm thick KEMOPOR EPS100 blocks, produced by the company Kamenović d.o.o., with a nominal density of 20 kg/m³;
- EPS 100 blocks were casted with 20 mm thick Keramzit (Liapor) C16/20 concrete with expanded clay aggregate, produced by the company Lias Österreich GesmbH;
- Keramzit (Liapor) concrete was reinforced with 50 × 50 mm grid galvanized mesh with 2 mm diameter bars over the entire bottom surface of the filling element ;
- measured moisture content in the concrete was 1,6 moisture content in % of dry weight.

Details of the test specimen are shown in the documentation provided by the sponsor in Annex No. 6.

3.5 Number of test specimens

The test was performed at the same time on one test specimen.

3.6 Applied loading

The 200 mm thick semi pre-fabricated lightweight loadbearing concrete ceiling slab **MARANA EUROPAN** was loaded using 112 weights, each with a weight of 20 kg, equally distributed over the surface of the test specimen. By the request of the sponsor the test load applied on the test specimen surface was 150 kg/m².

Details of the distribution of the loading are shown in the drawing in Annex No. 1.

4. Conditioning of the specimen

Before the test the test specimen was for 33 days in the Fire laboratory where the temperature was around 17 °C and relative humidity around 54 %.

5. Date of test

25th April 2023

6. Testing procedure

The test was carried out according to SIST EN 1363-1:2020 (identical to EN 1363-1:2020) and SIST EN 1365-2:2014 (identical to EN 1365-2:2014).

Representatives of the customer were present at the test.

6.1 Test conditions

- the furnace 4000 × 6000 and 4000 deep was oil and gas fired;
- the ambient temperature at the commencement of the test: 17 °C;
- air moisture content at the commencement of the test: 54 %.

6.2 Temperature inside the furnace

The temperature inside the furnace was measured by means of ten plate thermocouples NiCr-Ni. These thermocouples extended through the aerated concrete slabs into the burning space to approximately 100 mm from the exposed face of the test specimen. The furnace temperature rise was continuously controlled such that it follows the standard time-temperature curve within the accuracy specified in EN 1363-1:2020:

$$T = 345 \log_{10}(8t + 1) + 20$$

T temperature inside the furnace in °C
t time in minutes

The sketch of the furnace temperature measuring points is in Annex No. 1.

The diagram and the table of the temperatures inside the furnace are in Annex No. 2.

6.3 Preliminary measurements

During the specimen construction the construction details were verified and proved to be in concordance with enclosed documentation.

6.4 Overpressure inside the furnace

The overpressure inside the furnace was measured by means of one pressure transducer Furness Controls FCO432, computer and appropriate software. It was controlled by means of three dampers inside the exhaust in such a way that the overpressure inside the furnace 100 mm below the exposed face of the test specimen was approximately 20 Pa. The pressure was measured approximately 0,9 m below the exposed face of the test specimen, so that the target pressure at the measuring location was 13,2 Pa.

The diagram of the overpressure measuring is in Annex No. 3.

6.5 Temperature rise on the unexposed surface of the test specimen

The temperature rise on the unexposed face of the test specimen was measured by means of 11 thermocouples NiCr-Ni. The thermocouples for surface temperature measurement consist of a 0.2 mm thick by 12 mm diameter copper discs, to which 0.5 mm in diameter NiCr-Ni thermocouples are soldered. The thermocouples were covered with a 30 mm square by 2 mm thick insulating pads of density approximately 900 kg/m³ regarding to standard EN 1363-1:2020. All thermocouples were kept in position by means of inorganic glue.

The temperature rise was measured at the following points on the unexposed face:

Measuring of the average temperature rise (criteria 140K) and maximum temperature rise (criteria 180K):

Measuring point No. 1 at the centre of the test specimen;

Measuring points No. 2 to 5..... at the centre of each of the four quarters of the test specimen;

Measuring of the maximum temperature rise (criteria 180K):

Measuring points No. 6 and 7 in line with precast loadbearing ceiling beams, thermocouple at the centre of a beam, in line with measuring points 2 and 3;

Measuring points No. 8 and 9.....in line with precast loadbearing ceiling beams, thermocouple at the centre of a beam, in line with measuring point 1;

Measuring points No. 10 and 11.....in line with precast loadbearing ceiling beams, thermocouple at the centre of a beam, in line with measuring points 4 and 5.

The sketch of the unexposed face temperature measuring points is in Annex No. 1.

The diagrams and the tables of the temperature rise on the unexposed face of the test specimen are in Annex No. 4.

6.6 Deflection of the test specimen

Throughout the test the measurements of the deflection of the test specimen with accuracy ± 0.5 mm were made. Dimensions used for calculations were measured directly on the test specimen.

Failure is deemed to have occurred when, after the commencement of the test;

Limiting deflection:
$$D_{limit} = \frac{L^2}{400 \cdot d} = \frac{6400^2}{400 \cdot 210} = 487,6 \text{ mm}$$

and

Limiting rate of deflection:
$$\left(\frac{dD}{dt}\right)_{limit} = \frac{L^2}{9000 \cdot d} = \frac{6400^2}{9000 \cdot 210} = 21,7 \text{ mm/min}$$

are exceeded, or when measured deflection is greater than $1,5 \cdot D_{limit}$.

Maximum deflection: $D = 1,5 \cdot D_{limit} = \frac{1,5 \cdot L^2}{400 \cdot d} = \frac{1,5 \cdot 6400^2}{400 \cdot 210} = 731,4 \text{ mm}$

The sketch of the deflection measuring points is in Annex No. 1.

6.7 Deviations from the testing procedure

Due to the furnace error, the furnace burners shut down several times during the testing time. The burners shut down six times; in 21st, 48th, 59th, 75th, 96th and 106th minute. As a result of shut down burners, the standard time-temperature curve (described in Clause 6.2) limits were exceeded. The testing time was extended to cover the period when the furnace temperature was not in the limits, to reach fully valid testing conditions for classification time 90 minutes.

7. Observations during the test

7.1 Visual observation

TIME [min]	SIDE	OBSERVATION
0		The test commenced;
15		Smoke leakage at the short edge;
122		The test was discontinued on the sponsor's request.

7.2 Deflection of the test specimen

The deflection of the test specimen was measured at three positions. Measuring points I and III were positioned at mid-width of the test specimen at one third of the span length. Measuring point II was positioned at the centre of the test specimen.

The test specimen was loaded for at least 15 minutes before the commencement of the test.

The positive values mean bending of the test specimen into the furnace.

Time [min]	DEFORMATION ON MEASURING POINT [mm]			Remark
	I	II	III	
/	0	0	0	before the load was applied (*note: at least)
/	1	5	3	after the load was applied (*note: at least)
/	1	5	3	after the load was applied for 20 minutes
/	1	5	3	after the load was applied for 40 minutes
0	0	0	0	deformations: after the test commenced
1	0	0	0	
5	6	9	7	
9	17	24	17	
13	24	33	25	
17	29	38	29	
21	33	43	33	
25	37	48	37	
29	43	58	43	
33	52	70	52	
37	62	83	61	
41	71	95	71	

Time [min]	DEFORMATION ON MEASURING POINT [mm]			Remark
	I	II	III	
45	79	107	80	
49	87	118	88	
53	93	125	94	
57	99	134	101	
61	107	144	109	
65	110	150	112	
69	117	158	119	
73	123	167	127	
77	128	174	132	
81	129	175	133	
85	131	179	135	
89	138	187	141	
93	144	196	147	
97	150	204	153	
101	153	208	157	
105	158	216	162	
109	165	226	168	
113	170	232	172	
117	178	243	180	
121	186	254	189	

7.3 Integrity

The integrity of the test specimen was not lost during the testing time.

7.4 Insulation

The average temperature rise 140 K on the unexposed face of the test specimen was not exceeded during the testing time.

The maximum temperature rise 180 K on the unexposed face of the test specimen was not exceeded during the testing time.

7.5 Load-bearing capacity

The load-bearing capacity of the test specimen was not lost during the testing time.

8. Test results

NOTE: As described in the Clause 6.7 the testing time was intentionally extended to cover the testing time where the temperature conditions in the furnace was not reached, to achieve fully valid testing conditions for classification time of 90 minutes.

INSULATION - I:	Average temperature	90 minutes, no failure
	Maximum temperature	90 minutes, no failure

INTEGRITY - E:	Sustained flaming	90 minutes, no failure
	Cotton pad test	90 minutes, no failure
	Gap gauge ϕ 6 mm	90 minutes, no failure
	Gap gauge ϕ 25 mm	90 minutes, no failure

LOADBEARING CAPACITY - R:	Maximum deflection	90 minutes, no failure
---------------------------	--------------------	------------------------

Maximum rate of deflection 90 minutes, no failure
and deflection

This report details the method of construction, the test conditions and the results obtained when the specific element of construction described herein was tested following the procedure outlined in EN 1363-1, and where appropriate EN 1363-2. Any significant deviation with respect to size, constructional details, loads, stresses, edge or end conditions other than those allowed under the field of direct application in the relevant test method is not covered by this report.

Because of the nature of fire resistance testing and the consequent difficulty in quantifying the uncertainty of measurement of fire resistance, it is not possible to provide a stated degree of accuracy of the result.

9. Field of direct application of tested results

The test results are directly applicable to similar constructions where one or more of the changes listed below are made and the construction continues to comply with the appropriate design code for its stiffness and stability. Other changes are not permitted.

9.1 Moments and shear forces

The maximum moments and shear forces, which when calculated on the same basis as the test load, shall not be greater than those tested.

10. Annexes

- 1 temperature and deflection measuring points and load distribution (2 pages)
- 2 diagram and table of furnace temperature rise (2 pages)
- 3 diagram of overpressure in the furnace (1 page)
- 4 diagrams and tables of temperatures in the test specimen and temperature rise on the unexposed face (4 pages)
- 5 ambient temperature (1 page)
- 6 documentation provided by the sponsor (8 pages)
- 7 19 photographs (10 pages):

Photo No. 046997d-001: test specimen supporting construction

Photo No. 046997d-002: test specimen laid on the supporting construction

Photo No. 046997d-019: test specimen placed on the test frame and slabs placed at the longer edges

Photo No. 046997d-025: measuring of moisture content in the test specimen

Photo No. 046997d-020: short edge of the test specimen

Photo No. 046997d-027: exposed face before the commencement of the test

Photo No. 046997d-028: exposed face before the commencement of the test

Photo No. 046997d-029: exposed face before the commencement of the test

Photo No. 046997d-050: loaded test specimen at the commencement of the test

Photo No. 046997d-058: 16th minute of the test

Photo No. 046997d-069: 30th minute of the test

Photo No. 046997d-081: 46th minute of the test

Photo No. 046997d-094: 61st minute of the test

Photo No. 046997d-123: 91st minute of the test

Photo No. 046997d-151: 122nd minute of the test

Photo No. 046997d-155: unexposed face at the end of the test



Photo No. 046997d-161: exposed face at the end of the test

Photo No. 046997d-162: exposed face at the end of the test

Photo No. 046997d-163: exposed face at the end of the test


Report was prepared by: Simon Grum, mag. inž. str.

TEMPERATURE AND DEFLECTION MEASURING POINTS




- Thermocouples for average temperature rise (criteria 140K) and maximum temperature rise (criteria 180K)
- Thermocouples for maximum temperature rise (criteria 180K)
- Deformation measuring points
- Plate thermocouples for furnace control

LOAD DISTRIBUTION



FURNACE TEMPERATURE




NOTE: The burners shut down six times during the testing time, in 21st, 48th, 59th, 75th, 96th and 106th minute. The testing time was extended to cover the period when the furnace was shut down.


FURNACE TEMPERATURE

Time [min]	Requested furnace temp. [°C]	Average furnace temp. [°C]	Tolerance [%]	Percentage deviation [%]
0	20	20		
4	544	700		28,75
8	645	656	± 15	14,06
12	705	689	± 14	7,95
16	748	731	± 12	5,04
20	781	748	± 10	2,93
24	809	753	± 8	1,05
28	832	853	± 6	1,30
32	851	858	± 4,8	1,22
36	869	859	± 4,5	0,91
40	885	879	± 4,1	0,73
44	899	899	± 3,8	0,65
48	912	911	± 3,5	0,57
52	924	915	± 3,1	0,43
56	935	988	± 2,8	0,87
60	945	867	± 2,5	0,16
64	955	1000	± 2,5	0,49
68	964	1011	± 2,5	0,79
72	973	994	± 2,5	0,88
76	981	739	± 2,5	-0,67
80	988	795	± 2,5	-1,76
84	996	1029	± 2,5	-1,48
88	1003	1034	± 2,5	-1,24
92	1009	1030	± 2,5	-1,07
96	1016	813	± 2,5	-1,97
100	1022	1032	± 2,5	-1,84
104	1028	1068	± 2,5	-1,58
109	1034	828	± 2,5	-2,48
113	1040	1047	± 2,5	-2,35
117	1045	1083	± 2,5	-2,11
121	1050	900	± 2,5	-2,57

OVERPRESSURE IN THE FURNACE




TEMPERATURE RISE ON THE UNEXPOSED FACE



AVERAGE AND MAXIMUM TEMPERATURE RISE ON THE UNEXPOSED FACE

Time [min]	Temperature on measuring points 1 to 5 [K]					Average temp. [K]	Maximum temp. [K]
	TC1(°C)	TC2(°C)	TC3(°C)	TC4(°C)	TC5(°C)		
0	0,2	-0,6	-0,4	0,0	0,2	-0,2	0,2
4	0,2	-0,6	-0,3	0,1	0,1	-0,1	0,2
8	0,1	-0,6	-0,4	0,1	0,1	-0,2	0,1
12	0,1	-0,6	-0,4		0,1	-0,2	0,1
16	0,1	-0,6	-0,4	0,0	0,1	-0,2	0,1
20	0,0	-0,6	-0,4	-0,1	0,0	-0,2	0,0
24	0,1	-0,6	-0,4	-0,1	0,0	-0,2	0,1
28	0,2	-0,6	-0,3	-0,1	0,0	-0,2	0,2
32	0,3	-0,6	-0,3	-0,1		-0,2	0,3
36	0,4	-0,5	-0,2	0,0	0,1	-0,1	0,4
40	0,6	-0,5	-0,1	0,1	0,1	0,0	0,6
44	1,3	-0,2	0,3	0,5	0,3	0,4	1,3
48	3,0	0,5	1,6	1,7	0,7	1,5	3,0
52	5,5	2,0	3,7	3,6	1,6	3,3	5,5
56	8,4	4,0	6,4	6,1	3,2	5,6	8,4
60	11,6	6,4	9,4	8,8	5,6	8,3	11,6
64	14,9	8,9	12,4	11,6	8,3	11,2	14,9
68	18,3	11,5	15,5	14,4	11,1	14,2	18,3
72	21,8	14,2	18,5	17,2	14,0	17,1	21,8
76	25,4	16,7	21,5	20,0	16,8	20,1	25,4
80	29,2	19,2	24,4	22,7	19,6	23,0	29,2
84	33,0	21,7	27,2	25,4	22,4	25,9	33,0
88	37,0	24,0	29,9	28,0	25,1	28,8	37,0
92	41,0	26,3	32,6	30,5	27,6	31,6	41,0
96	45,0	28,5	35,2	33,0	30,3	34,4	45,0
100	48,7	30,7	37,7	35,3	32,7	37,0	48,7
104	52,7	32,8	40,2	37,8	35,1	39,7	52,7
109	57,2	35,3	43,2	40,5	37,7	42,8	57,2
113	60,6	37,5	45,8	42,8	40,1	45,3	60,6
117	64,0	39,6	48,3	45,4	42,5	48,0	64,0
121	67,1	41,9	50,9	47,9	44,8	50,5	67,1


MAXIMUM TEMPERATURE RISE ON THE UNEXPOSED FACE




MAXIMUM TEMPERATURE RISE ON THE UNEXPOSED FACE

Time [min]	Temperature on measuring points 6 to 11 [K]						Maximum temp. [K]
	TC6(°C)	TC7(°C)	TC8(°C)	TC9(°C)	TC10(°C)	TC11(°C)	
0	0,0	0,1	0,2	0,0	0,1	0,3	0,3
4		0,0	0,2	0,0	0,1	0,4	0,4
8	0,0	0,0	0,2	0,0	0,1	0,4	0,4
12	0,0	0,1	0,1	-0,1		0,3	0,3
16	-0,1	0,0	0,1	0,0	0,0	0,3	0,3
20	-0,1	0,0	0,1	0,0	-0,1	0,3	0,3
24	-0,1	0,0	0,1	-0,1	0,0	0,3	0,3
28	-0,1	0,0	0,2	0,0	-0,1	0,2	0,2
32	-0,1	0,1	0,2	0,1	-0,1	0,3	0,3
36	0,0	0,2	0,4	0,2	0,0	0,3	0,4
40	0,1	0,3	0,5	0,4	0,1	0,4	0,5
44	0,3	0,6	0,8	0,6	0,3	0,6	0,8
48	0,5	0,9	1,1	1,0	0,6	0,9	1,1
52	0,9	1,5	1,8	1,7	0,9	1,1	1,8
56	1,5	2,4	2,9	2,9	1,3	1,6	2,9
60	2,4	3,9	4,8	4,8	2,1	2,5	4,8
64	3,9	6,0	7,2	7,1	3,3	3,8	7,2
68	5,9	8,6	10,0	9,8	5,2	5,6	10,0
72	8,1	11,4	12,9	12,6	7,5	7,7	12,9
76	10,5	14,4	15,8	15,5	10,0	10,2	15,8
80	13,0	17,2	18,7	18,3	12,6	12,7	18,7
84	15,4	20,1	21,5	21,1	15,3	15,2	21,5
88	17,9	22,9	24,2	23,8	18,0	17,8	24,2
92	20,3	25,7	26,8	26,4	20,5	20,3	26,8
96	22,7	28,4	29,4	29,0	23,1	22,7	29,4
100	25,0	30,7	31,6	31,5	25,5	25,0	31,6
104	27,2	33,1	33,9	33,8	27,8	27,3	33,9
109	29,7	35,8	36,7	36,5	30,4	29,8	36,7
113	31,8	37,9	38,9	38,9	32,6	31,9	38,9
117	33,8	40,0	41,4	41,2	34,6	33,9	41,4
121	35,8	42,2	43,7	43,6	36,7	35,8	43,7


AMBIENT TEMPERATURE




DOCUMENTATION PROVIDED BY THE SPONSOR




DOCUMENTATION PROVIDED BY THE SPONSOR



DOCUMENTATION PROVIDED BY THE SPONSOR



DOCUMENTATION PROVIDED BY THE SPONSOR



DOCUMENTATION PROVIDED BY THE SPONSOR



TRIAL d.o.o., Terzićeva 17, Split
OIB:64026545644
Laboratorij: Sv. Liberana 48, Split
mob. +385 989844433

IZVJEŠTAJ O ISPITIVANJU
TLAČNE ČVRSTOĆE

Ob-7/1-3
Izdanje: 4
Revizija 0
12.11.2021.

Datum izvještaja: 29.11.2021

OPĆI PODACI:

Naziv i adresa naručitelja: MARANA d.o.o., Kurtovići 21, 21231, Klis
Naziv i adresa izvođača: MARANA d.o.o., Kurtovići 21, 21231, Klis
Ugovor/Narudžbenica: /
Građevina: Radni pogon „Marana“ Kurtovići 21, Klis

Građevni proizvod

PODACI O BETONU

Mjesto proizvodnje betona: MEGRAM – Sinj
Razred tlačne čvrstoće: C25/30

Tip betona: projektirani beton

PODACI O UZORCIMA

Mjesto izrade uzorka: gradilište

Uzorkovano prema: normi HRN EN 12390-2

Uzorkovao predstavnik: naručitelj

Dostavio predstavnik: naručitelj

Oblik i nazivne dimenzije uzorka: kocka 150*150*150 mm

Njegovanje od zaprimanja: u laboratorijskim uvjetima

Oznaka uzorka		Datum izrade (podatak naručitelja)	Konstruktivni element (podatak naručitelja)	Razred tlačne čvrstoće	Datum primitka	Stanje uzorka po primitku
Laboratorij	Naručitelj					
1.	1.	21.10.2021	Međukatna konstrukcija – testni uzorak	C25/30	24.11.2021.	zagladena, neoštećena, suha

REZULTATI ISPITIVANJA

Ispitano svojstvo: Tlačna čvrstoća očvrstlog betona prema HRN EN 12390-3:2019

Zasićenost uzorka: Vodom zasićen

Odstupanje od norme: /

Laboratorij. oznaka uzorka	Datum ispitivanja	Starost (dana)	Obrada ploha (brušenje/namaz)	DIMENZIJE IZMJERENE (mm)			Stanje površine u vrijeme ispitivanja	Oblik loma*	Gustoća ** (kg/m³)	Sila loma (kN)	Tlačna čvrstoća (N/mm²) f _{cd}
				a	b	h					
1.	26.11.2021	36	/	149,8	149,8	149,9	zagladena, neoštećena, suha	Z	2,33	785,1	35,0

Napomene:

* Z-zadovoljavajući lom, Nx - nezadovoljavajući lom, x je broj (1...9) prema sl. 1-2 HRN EN 12390-3

**Gustoća izračunata iz mase u zatečenom stanju i volumena iz izmjera, prema HRN EN 12390-7 - nije u području akreditacije.

Izjava: Uzorci su ispitani u skladu s normom, osim navedenog u točki "Odstupanje od norme"

Voditelj laboratorija:
Romeo Bartulović

Rezultat ispitivanja se odnosi isključivo na ispitane uzorke
Umnožavanje nije dozvoljeno bez pismenog odobrenja Voditelja laboratorija.

1

DOCUMENTATION PROVIDED BY THE SPONSOR



Kemenović d.o.o. hidro i toplinske izolacije · HR 10250 Zagreb · Lučko · Franje Puškarića 104a
tel. 01 6530 812, 6530 813 · fax. 01 6530 814 · www.kemenovic.com · kemenovic@zg.t-com.hr
MB: 3462935 · Žiro račun: 2360000 - 1101229096 Zagrebačka banka
Članovi uprave: Dušanka Kemenović, Dragan Kemenović
Trgovački sud u Zagrebu · MBS: 080145720 · Temeljni kapital 850.000,00 kn



IZJAVA O SUKLADNOSTI

U skladu s člankom 27. Zakona o gradnji ("Narodne novine" br. 175/03 i 100/04), člankom 31. Pravilnika o ocjenjivanju sukladnosti, ispravama o sukladnosti i označavanju građevnih proizvoda ("Narodne novine" br. 1/05),

KEMENOVIC d.o.o.
Puškarićeva 104a
HR - 10250 Zagreb

izjavljuje da je

toplinsko-izolacijski proizvod od ekspaniranog polistirena trgovačkog naziva:

KEMPOR EPS 100

Oznake: EPS-HRN EN 13163-T1-L1-W1-S1-P3-BS150-DS(N)5-WL(T)3-CS(10)100

proizveden u tvornici:

KEMENOVIC d.o.o.
Puškarićeva 104a
HR - 10250 Zagreb

sukladan zahtjevima norme:

HRN EN 13163:2002

Izjava se daje na osnovu provedenih radnji ocjenjivanja sukladnosti određenih normom HRN EN 13172:2002 i HRN EN 13172/A1:2005 za sustav ocjenjivanja sukladnosti 3 koje je proveo:
INSTITUT GRAĐEVINARSTVA HRVATSKE d.d., Zagreb, Janka Rakuše 1.

Evidencijski broj ovlaštene osobe: 1/05.

Ovlaštenje izdalo Ministarstvo zaštite okoliša, prostornog uređenja i graditeljstva: za radnje početnog ispitivanja tipa: Klasa: UP/I 360-01/05-08/00013, Urbroj: 531-01-06-10 od 22. ožujka 2006.

Direktor:
Dragan Kemenović, ing. građ.

Klasa: 360-02/07-1/4
Urbroj: 375-3462935-01-07-4

Zagreb, 10. studenog 2007.

DOCUMENTATION PROVIDED BY THE SPONSOR

**AMT DER WIENER LANDESREGIERUNG
Zertifizierungsstelle für Bauprodukte
WIEN - ZERT**

1110 Wien, Rinnböckstraße 15
 Telefon: (+431)79514-39385, Telefax: (+431)79514-99-8039
 E-Mail: zert.bau@post.wien.gv.at
 DVR 0000191

**EG - ZERTIFIKAT
über die werkseigene Produktionskontrolle**

**1139-CPD-0275/04
(3. Neufassung)**

Gemäß der Richtlinie des Rates der Europäischen Gemeinschaften vom 21. Dezember 1988 zur Angleichung der Rechts- und Verwaltungsvorschriften der Mitgliedsstaaten über Bauprodukte - 89/106/EWG - (Bauproduktenrichtlinie - BPR), geändert durch die Richtlinie des Rates der Europäischen Gemeinschaften vom 22. Juli 1993 - 93/68/EWG -, umgesetzt im Land Wien durch das Gesetz über Bauprodukte und die Akkreditierung von Prüf-, Überwachungs- und Zertifizierungsstellen für Bauprodukte in Wien (Wiener Bauprodukte- und Akkreditierungsgesetz - WBAG), LGBl. für Wien Nr. 30/1996 idgF. wird bestätigt, dass die Bauprodukte

**Leichte Gesteinskörnungen
(gemäß Angaben im Anhang zu diesem Zertifikat)**

in Verkehr gebracht durch

**Lias Österreich GmbH
A-8350 Fehring, Fabrikstraße 11**

und hergestellt im Werk

**Lias Österreich GmbH
A-8350 Fehring, Fabrikstraße 11**

einer Erstprüfung der Produkte durch den Hersteller unterzogen wurden sowie einer werkseigenen Produktionskontrolle und zusätzlichen Prüfungen von im Werk entnommenen Proben nach festgelegtem Prüfplan durch den Hersteller unterzogen werden und dass die notifizierte Stelle (Kennnummer 1139)

**Amt der Wiener Landesregierung - Zertifizierungsstelle für Bauprodukte
A-1110 Wien, Rinnböckstraße 15**

die Erstinspektion des Werkes und der werkseigenen Produktionskontrolle durchgeführt hat und die laufende Überwachung, Beurteilung und Anerkennung der werkseigenen Produktionskontrolle durchführt.


Dieses Zertifikat bestätigt, dass alle Vorschriften betreffend die Bescheinigung der Konformität der werkseigenen Produktionskontrolle, beschrieben im Anhang ZA der Norm

EN 13055-1:2002/AC:2004

angewendet wurden.


Dieses Zertifikat wurde erstmals am 18. Februar 2005 ausgestellt. Die vorliegende 3. Neufassung des Zertifikats 1139-CPD-0275/04 ersetzt die 2. Neufassung des Zertifikats vom 04. April 2011 und gilt solange sich die Festlegungen in der oben angeführten harmonisierten europäischen Norm nicht geändert oder die Herstellbedingungen im Werk oder die werkseigene Produktionskontrolle selbst nicht wesentlich verändert haben. Das Zertifikat umfasst inklusive Anhang zwei Seiten.

Der Zeichnungsberechtigte:


 Dipl.-Ing. Bernhard Ramsauer



Der Leiter der Zertifizierungsstelle:


 Dr. Peter Proßegger
 Oberstadtbaurat

Wien, 07. Oktober 2011

2011-0717

DOCUMENTATION PROVIDED BY THE SPONSOR

	TRIAL d.o.o., Terzićeva 17, Split OIB:64026545644 Laboratorij: Sv. Liberana 48, Split mob. +385 989844433	IZVJEŠTAJ O ISPITIVANJU TLAČNE ČVRSTOĆE		Ob-7/3-1 Izdanje: 5 Revizija 0 7.7.2022

BROJ IZVJEŠTAJA: LT-2022-304

Datum izvještaja: 28.10.2022

OPĆI PODACI:

Naziv i adresa naručitelja: MARANA d.o.o., Kurtovići 21, 21231 Klis
 Naziv i adresa izvođača: MARANA d.o.o., Kurtovići 21, 21231 Klis
 Ugovor/Narudžbenica: /

Građevina: RADNI POGON MARANA

Građevni proizvod

PODACI O BETONU (Podaci Naručitelja)

Mjesto proizvodnje betona: Gradilište
 Razred tlačne čvrstoće: C16/20 Tip betona: projektirani beton

PODACI O UZORCIMA

Mjesto izrade uzorka: gradilište Uzorkovano prema: normi HRN EN 12390-2
 Uzorkovao predstavnik: naručitelja Dostavio predstavnik: naručitelja
 Oblik i nazivne dimenzije uzorka: kocka 150*150*150 mm
 Njegovanje od zaprimanja: u laboratorijskim uvjetima

Oznaka uzorka		Datum izrade (podatak naručitelja)	Konstrukcijski element (podatak naručitelja)	Razred tlačne čvrstoće	Datum primitka	Stanje uzorka po primitku
Laboratorij	Naručitelj					
TM356-1	1.	10.9.2022	ISPUNA ZA MEĐUKATNU/ KROVNU KONSTRUKCIJU	C16/20	27.10.2022.	zagladena, neoštećena, suha
TM356-2	2.	10.9.2022	ISPUNA ZA MEĐUKATNU/ KROVNU KONSTRUKCIJU	C16/20	27.10.2022.	zagladena, neoštećena, suha

REZULTATI ISPITIVANJA

Ispitano svojstvo: Tlačna čvrstoća očvrslog betona prema HRN EN 12390-3:2019
 Zasićenost uzorka: Vodom zasićen
 Odstupanje od norme: /

Laboratorij, oznaka uzorka	Datum ispitivanja	Starost (dana)	Obrada ploha (brušenje/ namaz)	DIMENZJE IZMJERENE (mm)			Stanje površine u vrijeme ispitivanja	Oblik loma*	Gustoća ** (kg/m³)	Sila loma (kN)	Tlačna čvrstoća (N/mm²)
				a	b	h					fc
TM356-1	28.10.2022	48	/	149,2	149,8	149,4	zagladena, neoštećena, suha	Z	1,63	497,9	22,3
TM356-2	28.10.2022	48	/	151,0	150,4	149,8	zagladena, neoštećena, suha	Z	1,63	457,2	20,1

Napomene:

* Z-zadovoljavajući lom, Nx - nezadovoljavajući lom, x je broj (1...9) prema sl. 1-2 HRN EN 12390-3

**Gustoća izračunata iz mase u zatečenom stanju i volumena iz izmjera, prema HRN EN 12390-7 - nije u području akreditacije.

Izjava: Uzorci su ispitani u skladu s normom, osim navedenog u točki "Odstupanje od norme"

Voditelj laboratorija:
Roko Gudelj

Rezultat ispitivanja se odnosi isključivo na ispitane uzorke
 Umnožavanje nije dozvoljeno bez pismenog odobrenja Voditelja laboratorija.

1

PHOTOS



Photo No. 046997d-001: test specimen supporting construction



Photo No. 046997d-002: test specimen laid on the supporting construction



Photo No. 046997d-019: test specimen placed on the test frame and slabs placed at the longer edges



Photo No. 046997d-025: measuring of moisture content in the test specimen



Photo No. 046997d-020: short edge of the test specimen



Photo No. 046997d-027: exposed face before the commencement of the test



Photo No. 046997d-028: exposed face before the commencement of the test




Photo No. 046997d-029: exposed face before the commencement of the test



Photo No. 046997d-050: loaded test specimen at the commencement of the test



Photo No. 046997d-058: 16th minute of the test

Photo No. 046997d-069: 30th minute of the testPhoto No. 046997d-081: 46th minute of the test

Photo No. 046997d-094: 61st minute of the testPhoto No. 046997d-123: 91st minute of the test

Photo No. 046997d-151: 122nd minute of the test

Photo No. 046997d-155: unexposed face at the end of the test



Photo No. 046997d-161: exposed face at the end of the test



Photo No. 046997d-162: exposed face at the end of the test



Photo No. 046997d-163: exposed face at the end of the test